

# **febie**XAKT



# Multi-V Belt Kit

febi no. 40308

OE No. 03L 903 137 T S1



fits

Audi, VW, Seat and Škoda 1,6 TDI and 2.0 TDI engines with common-rail injection system

### >> PROBLEM:

The flexible multi-V belt 6EPK1140 for the engines referred to above is no longer installed and the new belt 6PK1070 cannot be fitted directly.

## >> CAUSE:

The original version of the auxiliary drive was powered via the flexible multi-V belt and the deflection pulley (Fig. 1). To improve the running characteristics, vehicle manufacturers have developed a new design for the auxiliary drive.


### >> SOLUTION:


Instead of a flexible belt and the deflection pulley, the modified version uses a new multi-V belt and a tensioning element (Fig. 2). For this reason, in addition to the components that are available individually, febi bilstein also offers a complete multi-V belt kit (febi no. 40308) which also includes the mounting screw as well as the new belt (febi no. 37533) and the belt tensioner (febi no. 27618).





febi no. 37533





Ferdinand Bilstein GmbH + Co. KG

Wilhelmstr. 47 | 58256 Ennepetal | Germany

Tel. +49 2333 911-0 Fax +49 2333 911-444 E-Mail info@febi.com

febi is a bilstein group brand

